Rosemead/Lakewood Blvd Complete Corridor Vision Plan Task 5.2 adjustments – December 2024

October 7, 2024 RFP Scope of Work:

Task 5.2 - Implementation and Funding Strategy

1. The consultant will prepare a phased implementation plan that identifies and proposes physical improvements, operations and maintenance considerations, phasing, cost estimates, and steps for pursuing funds for planning, approval, environmental documentation, full design, and construction. It will identify local, regional, state, and federal funding and financing strategies and sources with details on what each one can address such as capital improvements, feasibility analysis, environmental review, property acquisition, engineering design and construction documents, vehicles, maintenance, and operations. The plan will also include a proposed management strategy with prospective lead entities to carry the project beyond this initial planning stage.

2. *NEW SCOPE - December 3, 2024*

Based on a conversation with the City of Pico Rivera ("City") HDR understands a new subtask for Task 5.2 will be to facilitate support amongst corridor cities for an Early Action Plan for the project corridor as a priority network for the upcoming 2028 Olympic and Paralympic Games. The consultant will support development of the Early Action Plan with a feasibility analysis of implementing Transit Signal Priority (TSP) along the project corridor and an early striping and signage plan based on early acceptance by cities of allowing busonly lanes along certain sections along the corridor. TSP analysis is anticipated to include obtaining existing traffic signal information from each agency, coordinating with Metro on timing for establishing MOUs with each agency and the cost for signal priority cloud software, determining required signal equipment upgrades along the project corridor, and calculating the effort to re-time each signal. Early striping and signage plan feasibility analysis is anticipated to include review of existing and proposed striping for potential early implementation, determination of any signage modifications that would be required, and calculation of effort to produce the required plans and specifications within the broader project implementation strategy.

Task 5.2 Deliverables (updated December 2024):

- Report providing an explanation of TSP
- Draft outline of an early striping and signage plan
- Implementation strategy, including cost, schedule, and requirements for implementation (including TSP and early striping and signage plan)